



LJMU Research Online

Chippagiri, R, Bras, A and Ralegaonkar, RV

Development of sustainable prefabricated housing system by small-scale experimental model

<http://researchonline.ljmu.ac.uk/id/eprint/18155/>

Article

Citation (please note it is advisable to refer to the publisher's version if you intend to cite from this work)

Chippagiri, R, Bras, A and Ralegaonkar, RV (2022) Development of sustainable prefabricated housing system by small-scale experimental model. Proceedings of the Institution of Civil Engineers: Engineering Sustainability. pp. 1-14. ISSN 1478-4629

LJMU has developed **LJMU Research Online** for users to access the research output of the University more effectively. Copyright © and Moral Rights for the papers on this site are retained by the individual authors and/or other copyright owners. Users may download and/or print one copy of any article(s) in LJMU Research Online to facilitate their private study or for non-commercial research. You may not engage in further distribution of the material or use it for any profit-making activities or any commercial gain.

The version presented here may differ from the published version or from the version of the record. Please see the repository URL above for details on accessing the published version and note that access may require a subscription.

For more information please contact researchonline@ljmu.ac.uk

<http://researchonline.ljmu.ac.uk/>

Title: Development of sustainable prefabricated housing system by small-scale experimental model

Author 1

Ravijanya Chippagiri, Research scholar

Department of Civil Engineering at VNIT, Nagpur, India

ravijanya991@gmail.com (Corresponding Author)

ORCID Number: 0000-0002-1698-8282

Author 2

Ana Bras, PhD

Built Environment and Sustainable Technologies (BEST) Research Institute, Liverpool John

Moores University, UK

a.m.armadabras@ljmu.ac.uk

Author 3:

Rahul V. Ralegaonkar, PhD

Department of Civil Engineering at VNIT, Nagpur, India

sanvan28@yahoo.com

Abstract

Utilisation of unused industrial wastes and need for rapid volumetric construction led to the evolution of sustainable prefabricated housing elements, particularly for urban slums. An agro-industrial by-product as raw material and waste expanded polystyrene beads as the insulation material are chosen to develop a lightweight prefabricated construction element. This bio-ash is used as a partial replacement, 20% and 10% for the fine aggregates to prepare concrete and lightweight mix respectively. A small-scale model of one-third scale is conceptualised as per standards that include precast columns and beams as framed structure, and prefab panels as walling and roofing elements. These elements are developed as per the desired mix proportions of the identified raw materials. The respective laboratory specimens are evaluated for the physico-mechanical, durability, and thermal properties. The developed walling end-product is found to be 27% lighter, 8% stronger, 24% less water-absorbent, and 62% less conductive when compared with the properties of commercially available fly-ash brick. A solar photovoltaic panel is embedded into the model's pitch roof that accommodates 71% of its generated energy to necessary electrical appliances. The material properties are found to be satisfactory for its on-site application and its final erection being 20% faster than conventional method.

Keywords: Sustainability; lightweight concrete; precast concrete; modelling; strength and testing of materials.

1 **1. Introduction**

2 Increasing population across the globe has resulted for housing shortage. World Bank has
3 estimated a need of 300 million houses by the end of 2030 (Kulshreshtha *et al.*, 2020). Majority
4 of the housing shortage lies with urban population that may increase up to 60% by the end of 2030
5 (Grandoliniede and Ijjasz-Vasquez, 2016). India is currently the second-most populous country
6 with a population exceeding 1380 million at the end of 2020. The country’s urban population is
7 figured around 35%, which indicates the need of volumetric housing construction. The government
8 has taken an initiative scheme “Housing for all” which targets the construction of 20 million urban
9 houses by the end of 2022 (Department of Economic and Social Affairs, no date; Ministry of
10 Housing & Urban Poverty Alleviation Government of India, 2017). This scheme is mainly
11 focussed on the economically weaker section (EWS), and low income group (LIG).

12
13 Industrialisation and growing population have increased construction activities across the country.
14 The construction sector continues as the second largest industry and is mostly accountable for 30%
15 of CO₂ emissions, 32% of energy consumption, and 30-40% of waste generation (Ferdous *et al.*,
16 2019a). A report from the UN climate action summit 2019 mentions the nations to cut down their
17 CO₂ emissions to 45% by 2030 (United Nations, 2019). Rise in advanced technologies and the
18 requirement of proficient construction practices have led to rapid construction methods like
19 prefabrication technology. Prefabrication (prefab), is defined as the manufacturing of the
20 construction elements in a controlled industrial environment and installation of the same at desired
21 site (Steinhardt and Manley, 2016).

22

23 Construction in the urban areas is challenging in case of conventional methods because of densely
24 populated areas, cost, and time constraints (Dave, Watson and Prasad, 2017). Prefab technology
25 found to be advantageous when compared to the conventional construction methods. The specific
26 study resulted in 65% reduction in waste generation, 25% less manpower requirement, 15% time
27 saving, 14% reduction in greenhouse emissions and 63% reduction for accidents (Li, Shen and
28 Xue, 2014; Krishnanunny and K, 2018; Ferdous *et al.*, 2019b; Liu, Jia and Liu, 2019). However,
29 the technology needs higher investment and expertise for planning and execution.

30

31 Major materials involved in the traditional construction activities include steel, concrete, timber,
32 and bricks. One ton of manufacturing steel, cement, and burnt clay bricks each release around 2
33 tonnes, 0.95 tonnes, and 0.05 tonnes of CO₂ respectively in the environment (Van Ruijven *et al.*,
34 2016; Nath, Lal and Das, 2018; Gavali *et al.*, 2019). An increase in the construction activities and
35 industrialisation has led to the increase in exploitation of natural resources and generation of
36 industrial wastes. Managing these industrial rejects is considered as one of the major challenges.
37 [Industrial rejects is an alternate terminology for the industrial by-products or industrial wastes
38 (Kumar *et al.*, 2021)]. Thus, to balance these two aspects, the alternative to the natural resources
39 (sand) was explored by researchers using the by-products having the origin either as agro-based
40 (rice husk) or industrial based (coal residue), collectively termed as agro-industrial by-products
41 for the construction industry. The prior research encourages the application of sustainable
42 construction materials for the energy conservation inside the structures (Bras *et al.*, 2020). The
43 rejects like fly ash, silica fume, ground granulated blast furnace slag (industry-based), and rice
44 husk ash (agro-based) were already considered as mineral admixtures by the Indian standards.
45 Cement has been the major material in the construction industry and cement-based materials were

46 widely used all over the world for various cast in-situ and precast techniques. Three grades in
47 ordinary Portland cement (OPC), grades 33, 43, and 53 were approved in India for their
48 applications and specific standards were set up namely IS 269, IS 8112, and IS 12269 respectively.
49 Along with these, there were a few other types of cement partially mixed with fly ash and blast
50 furnace slag called as Portland pozzolana cement (PPC) and Portland slag cement (PSC)
51 respectively for its use at specific locations (Kumar Gangaram Singh and Kizhakkumodom
52 Venkatanarayanan, 2020; Singla, Kumar and Alex, 2020). Apart from these, many other
53 researchers have developed sustainable masonry products from sugarcane bagasse ash (SBA), bio-
54 briquette ash (BBA), re-cycled paper mill waste (RPMW), construction and demolition waste
55 (C&DW), and co-fired blended ashes (Raut *et al.*, 2012; Dakwale and Ralegaonkar, 2014;
56 Madurwar, Mandavgane and Ralegaonkar, 2015; Sakhare and Ralegaonkar, 2016a; Ram,
57 Ralegaonkar and Pradhan, 2017; Gavali and Ralegaonkar, 2020; Rathod *et al.*, 2020). In order to
58 conserve the operational energy demand of the structures, it is appropriate to design the building
59 materials with low thermal conductivity. The insulating materials like expanded polystyrene
60 (EPS), extruded polystyrene (XPS), polyurethane (PUR), polyisocyanurate (PIR), mineral wool,
61 MgO boards, foamed concrete, etc. are some of the examples that helped to improve the thermal
62 resistance of the building elements (Einea *et al.*, 1991; Correia, Ferreira and Branco, 2006; Naito
63 *et al.*, 2012; Shams *et al.*, 2015; Amran *et al.*, 2016; I. Goh *et al.*, 2016; Lopez and Froese, 2016;
64 Daniel Ronald Joseph, Prabakar and Alagusundaramoorthy, 2018; Flansbjer *et al.*, 2018).

65

66 In order to meet the increasing demand for the development of sustainable mass housing schemes,
67 it is apt to promote faster construction technology. From the reviewed literature, it is evident that
68 the manufacturing of construction materials using industrial ashes and insulation materials is a

69 feasible and sustainable solution. However, the development of sustainable prefab walling
70 technology using industrial ashes and insulation materials that are light in weight and having better
71 thermal insulation properties is one of the aspects to be researched. Thus, the present study
72 highlights the design and development of lightweight prefab walling material using agro-industrial
73 ash, CFA along with insulation material in a view to satisfy both sustainability and energy-
74 efficiency objectives. The small-scale modelling technique is used to demonstrate the
75 prefabricated housing technique.

76 **2. Materials and Methodology**

77 ***2.1 Materials***

78 The locally available agro-industrial ash (located 31 km from the city of Nagpur, India), obtained
79 by co-firing coal and saw dust (CFA) was identified as a raw material (Fig. 1). Research related to
80 this ash was carried out in various experimental studies by previous researchers. As the source
81 being the same, the material was found consistent with its properties even though acquired through
82 various seasons. The products like bricks (Ram, Ralegaonkar and Pradhan, 2017), mortar (Shelote
83 *et al.*, 2021), concrete (Chippagiri *et al.*, 2021), and alkali-activated masonry products (Gavali *et*
84 *al.*, 2019) were developed earlier. The design of modular prefabricated construction elements using
85 CFA is aimed in the present study. Fine aggregates are partially replaced with CFA to develop
86 precast components and lightweight prefab elements in this study. This raw material found in
87 compliance with the specified material characteristics as per section 7/part 6 of National Building
88 Code (NBC-2016) (BIS, 2016) to be used in prefabrication such as its easy availability, light in
89 weight, and better thermal insulation as compared to river sand.

90

91 Physical properties and chemical characterization are provided in Table 1. The specific gravity is
 92 determined with the volume displacement method as per IS 1727: 1967. The bulk density test is
 93 performed as mentioned in IS 2386 (Part 3): 1963. The chemical characterization of this raw
 94 material is determined from the chemical analysis done using X-ray fluorescence (XRF) scan
 95 which provides the oxides present in the material.



Figure 1. CFA



Figure 2. Fly Ash

96

97

Table 1. Properties of raw material – CFA.

Physical properties	Specific gravity	2.29					
	Color	Black					
	Bulk density	1430 kg/m ³					
Chemical characterization	Oxides	SiO ₂	Al ₂ O ₃	Fe ₂ O ₃	K ₂ O	SO ₃	CaO
	% Content	68.5	8.89	3.39	1.68	1.42	1.4

98

99 Along with the by-product, several other conventional materials such as cement, fly ash (Fig. 2),
 100 river sand, crush sand, and coarse aggregates are used in this study. Additionally, mixes are trialled

101 with a calcium-based accelerator, waste EPS beads, polymers such as hydroxypropyl
 102 methylcellulose (HPMC) and redispersible polymer (RDP), mineral, and chemical admixtures to
 103 obtain the targeted end-products.

104 **2.2 Mix Design/Proportion, Preparation of specimen**

105 Two different concrete mixes are proposed in this study. One for columns, beams & roof. The
 106 other lightweight (LW) concrete mix for the walling elements. Five trials for the concrete mix
 107 proportion (Table 2) and 11 trials for lightweight mix (Table 3) are performed by changing various
 108 combinations of the materials and their proportions. Each mix trial is tested for 6 specimens, 3
 109 each for both 7 day and 28 day average strength. Density and compressive strength are considered
 110 the priority parameters and the final mix is derived based on these properties. A density of 2200
 111 kg/m³ and 1300 kg/m³ was targeted for concrete and LW mix respectively. Similarly, an average
 112 compressive strength of 25 MPa and 7 MPa for concrete and LW mix respectively was chosen for
 113 the design. The LW mix is designed based on non-load bearing criteria and hence, the structural
 114 properties of this specific criteria was tested as per the codal provisions. The raw material is
 115 partially replaced with fine aggregate by 20% in concrete and by 10% in lightweight mix in the
 116 final mix proportion. Based on this, various samples are cast to test for physico-mechanical,
 117 durability, and thermal properties as per the codal standards (Table 4). The particle size graph of
 118 the materials used for LW mix are shown in the Figure 3.

119 **Table 2.** Mix design trials for concrete (All values in kg)

Trial No.	Cement	River Sand	CFA	20mm Gravel	10mm Gravel	Water	Aeration Agent (×10 ⁻³)	Admixture
-----------	--------	------------	-----	-------------	-------------	-------	-------------------------------------	-----------

C1	4.32	7.46	0	6.45	6.45	2.05	-	-
C2	4.32	5.97	1.49	6.45	6.45	2.05	-	-
C3	4.32	3.73	3.73	6.45	6.45	2.05	-	-
C4	3.92	5.424	1.356	5.86	5.86	1.86	0.3	0.012
C5	3.92	5.424	1.356	5.86	5.86	1.86	0.5	0.016

Table 3. Mix design trials for LW mix (All values in kg)


Trial No.	Premix							Premix	EPS beads ($\times 10^{-3}$)	Crush Sand	CFA	Water	Accel-erator ($\times 10^{-3}$)	Admix-ture ($\times 10^{-3}$)
	Cement	Fly Ash	Latex ($\times 10^{-3}$)	HPMC Polymer ($\times 10^{-3}$)	RDP Latex ($\times 10^{-3}$)	Micro Silica ($\times 10^{-3}$)	Calcium based Accelerator ($\times 10^{-3}$)							
LW1								0.973	26.78	3.000	-	0.300	-	
LW2	1.136	1.136	12.5	5	-	-	-	0.409	11.247	0.702	0.078	0.190	-	
LW3								0.818	22.5	0.504	0.056	0.290	-	
LW4								0.818	22.5	0.504	0.056	0.250	-	6.21
LW5	1.410	1.416	-	3	45	45	-	0.818	22.5	0.504	0.056	0.250	-	7.8
LW6								0.818	22.5	0.504	0.056	0.235	-	6.21
LW7								0.818	22.5	0.504	0.056	0.240	-	4.05
LW8	0.966	0.960	-	2	-	-	20	0.818	22.5	0.504	0.056	0.242	8.18	4.05
LW9								0.315	-	0.194	0.022	0.082	-	1.57
LW10								0.818	11.25	0.504	0.056	0.242	-	4.5
LW11	0.966	0.960	-	2	-	-	20	0.818	5.65	0.504	0.056	0.242	-	4.5
LW12	2.125	2.112	-	4.4	-	-	44	4.000	27.6	2.464	0.274	1.183	-	22

123

Table 4. Performance evaluation of developed end-product

Physico-mechanical properties	Standard procedure
Density	IS 2185 : 1979 (Part I)
Compressive strength	IS 2185 : 1979 (Part I)
Tensile strength	IS 5816 : 1999
Flexural strength	IS 516 : 1959
Water absorption	IS 2185 : 1979 (Part I)
Durability	Rapid chloride permeability test (ASTM C1202)
Thermal properties	Lee's Disc apparatus test (ASTM C177)

124




125

126

Figure 3. Particle size graph of the consumables of LW mix

127



128

Figure 4. Concrete trials – Trade-off between compressive strength and density

129


130

131 The concrete trials C1, C2, and C3 are done to find out the optimum percentage of raw material
 132 that can partially replace the fine aggregates. Mix C2 with 20% replacement gave better results
 133 (Fig. 4). This mix is further experimented to bring down its density by around 10% by adding
 134 aeration agents. Mix C5 gave better results with desired strength and lesser density.

135

136 The LW mix trials are carried out using various materials with varying proportions as mentioned
 137 earlier. A premix of cementitious materials is prepared firstly and then a part premix is utilized for
 138 the mix trials. Figure 5 represents the comparison graph of strengths and density. Mix LW1
 139 excludes the by-product to give an impression regarding the density and strength of the mix. Mix

140 LW9 excludes the EPS beads to realize the mortar's density and strength. LW11 was finalized as
 141 the mix and further LW12 is carried out for casting final specimens for testing.



142

143 **Figure 5.** LW mix trials – Trade-off between compressive strength and density

144 **2.3 Methodology**

145 The cubes, cylinders, beams, and discs are cast and tested according to the procedures laid by the
 146 standards as mentioned earlier. The test images are also presented in the Figures 6-8. The
 147 mechanical properties are tested by casting cubes for compressive strength, cylinders for split
 148 tensile strength, and beams for flexural strength (Fig. 6 (a, b, c)). Discs of 100mm diameter and

149 50mm thickness (Fig. 7) are cast to check the durability and thermal properties. Rapid chloride
150 permeability test (RCPT) is considered for checking the durability parameter of the end-products.

151 Lee's disc apparatus is used to evaluate the thermal conductivity of the products (Fig. 8).

152



(a) Compressive test



(b) Split tensile test



(c) Flexural test

Figure 6. Mechanical testing of concrete and lightweight mix

153



Figure 7. RCPT samples



Figure 8. Thermal Conductivity test

154 Based on the optimum mix proportion of the sustainable materials, a small-scale model house
155 exactly to one-third of the original plan as shown in the Figure 9 is constructed. This particular
156 model represents an urban slum house. As per the plan, structural elements such as beams and

157 columns are made of precast concrete. The prefab walling and roofing elements are cast with LW
 158 mix. Roofing is experimented with the LW panels as the model is designed for a pitched roof with
 159 no loads exerting on its top surface. The process of prefabrication starting from the manufacturing
 160 of elements to the final erection is followed by considering section 10/part 7 of NBC (2016) –
 161 volume 1 (BIS, 2016). The 3D drawings and elevations from different directions of the
 162 experimental model house are as shown in the Figure 10.




Figure 9. Line diagram of model house

163



164

165

Figure 10. Model house - drawings

166

The structural elements and prefab panels are coded as per the Table 5 given below. Accordingly,

167

the exterior elevations from four different directions along with their coded elements are presented

168

as shown in the Figure 11 (a, b, c, d).


169

Table 5. Code, size and number of concrete and prefab elements


Type	Code	Name	Size (m)	Required Nos.
Concrete	EC	External Column	0.1×0.1×0.9	6
	ESB	External Short Beam	2.83×0.1×0.1	3
	ELB	External Long Beam	1.58×0.1×0.1	4
	ELWP	External Long Wall Panel	1.43×0.45×0.07	8

	ESWP	External Short Wall Panel	1.315×0.45×0.07	8
	RP	Roof Panel	0.885×1.58×0.05	8
Light	TRP	Triangular Roof Panel	b=1.332, h=0.982, t=0.07	6
weight	ILWP	Internal Long Wall Panel	1.51×0.45×0.04	4
Mix	ISWP	Internal Short Wall Panel	1.48×0.45×0.04	2
	LBRP	Long Bathroom Panel	1.45×0.45×0.04	2
	SBRP	Short Bathroom Panel	0.6×0.45×0.04	2



170



(a) North elevation



(b) South elevation



(c) East elevation

(d) West elevation

Figure 11. Exteriors of model house as per coding of panels

171

172 In order to meet the operational energy demand, it is proposed that the on-site built in decentralised
173 energy generation approach be conceptualised for the model house. A pitch roof element is
174 designed to have a solar PV panel embedded into the roof making it an integrated component. The
175 angle of the roof was finalised at 37° as an optimum angle for generating maximum energy in the
176 area of Nagpur, India (Sakhare and Ralegaonkar, 2018). A solar photovoltaic (PV) panel (Table
177 6), 6×12 polycrystalline cells capable of producing 1 kW energy within 6.22 sq. m. of panel area
178 is integrated with a south-facing roof panel.

179

Table 6. Specifications of solar PV panel

Description	Specifications
Dimensions	1980 × 1010 × 14 ($\times 10^{-3}$)m
Weight of panel	45 kg
Max. power	320 W
Cell efficiency	18%
Units generated	215 units/sq.m./yr or 4.5 units/kW/yr
Thermal resistance	0.144 m ² K/W


180

181 **3. Results and Discussion**

182 Various tests revealed the suitability of concrete and LW mix. The physico-mechanical properties
183 of both the end-products are mentioned in Table 7 and Figure 12. Along with these, durability and
184 thermal properties are calculated and the final results of it are presented in Table 8.

Table 7. Physico-mechanical properties of developed end-products

S. No.	Property	Concrete	LW mix	Remarks (IS 456: 2000; IS:2185, 2005)	
1	Density (kg/m ³)	Dry	2302	1312	LW mix falls under Grade
2		7 day	15.87	5.68	B load bearing concrete
3	Compressive strength (MPa)	28 days	26.915	7.05	masonry unit as per IS 2185 (Part 1) : 2005
4	Split Tensile strength (MPa)	28 days	1.83	1.275	-
5	Flexural strength (MPa)	28 days	4.02	2.16	Satisfies the condition mentioned in IS 456 : 2000
6	Water Absorption (%)	24 hrs	5.77	7.64	Falls less than 10% as per IS 2185 (Part 1) : 2005



187


188

Figure 12. Physico-mechanical test results of developed mix

189

190 A study on stress-strain characteristics is conducted for the developed end-products. CFA-based concrete
 191 and LW mix cylinders are tested for compressive stress along with the strain values. Figure 13 indicates
 192 stress-strain plots for the developed products. Linearity in the curves is observed at the initial points of load
 193 followed by the non-linearity when the load increases further. After reaching their maximum stresses, a
 194 decline in the stress is observed with the increased strain value. The LW mix is designed as per the non-
 195 load bearing criteria and thus, its peak is observed at an early stress value than the CFA-based concrete.

196



197

198

Figure 13. Stress-strain curve of both the developed end-products

199

200

Table 8. Thermal and durability properties of developed end-products

S. No.	Property	Name of test	Concrete	LW mix	Remarks
1	Thermal	Thermal conductivity (W/mK)	0.806	0.40	-
2	Durability	Chloride permeability (Coulombs)	619.29	329.04	Chloride permeability lies in very low range

201

202 A comparative analysis is studied between the developed end-product and commercially available
 203 walling materials such as burnt clay bricks and fly ash bricks. The details of the properties were
 204 referred from earlier research (Sakhare and Ralegaonkar, 2016b) and compared with the developed
 205 end-product. The proposed lightweight prefab panel is found to have better properties in four
 206 categories as mentioned in Table 9.

207 **Table 9.** Comparative analysis between various walling materials

Walling Material	Density (kg/m ³)	Compressive strength (MPa)	Water absorption (%)	Thermal conductivity (W/mK)
Burnt clay brick	1600	7.0	15	1.25
Fly ash brick	1800	6.5	10	1.05
Lightweight prefab panel	1312	7.05	7.64	0.40

208

209 From the comparison, the prefab walling panel is found to be 18% lighter, 0.7% stronger, 49% less
 210 water absorbent, and 68% thermally efficient when compared with the burnt clay brick. Similarly,
 211 the designed end product results as 27% less dense, 8% stronger, 24% less water absorbent, and
 212 62% less conductive than the fly ash brick.

213

214 The energy generated from the installed solar PV panel on the top of model house is analysed.
 215 Based on its specifications mentioned earlier, the panel is capable of generating 2.56 kW-h of
 216 energy when 8 hours of daylight is considered as per Energy Conservation Building Code
 217 standards (ECBC, 2017). This can sufficiently accommodate a 75W ceiling fan and a 40W tube


218 light assuming the working hours as 18 hours and 12 hours respectively which is around 71% of
219 the generated energy.

220 **4 Small scale modelling**

221 The test results indicate their suitability in the construction industry resulting to execute a model
222 house as discussed earlier with these end products. Thus, the total construction of this model house
223 can be classified into 3 types which include works from raw material consumption to the final
224 erection of the model house.

225 ***4.1 Prior casting work***

226 As per the given plan of the structure, 6 columns and 7 beams are identified as structural elements.
227 A structural plan is presented in Figure 14 showing the column and beam placements. Along with
228 this, 40 prefab panels of varying dimensions are identified as walling and roofing members. The
229 concrete beams have male and female-type joints where each beam rests on another beam and are
230 jointed accordingly with the polymer-based epoxy grout. Similarly, roofing elements of south
231 elevation have grooves for the PV panel to fit in the panels as an integrated solar PV panel roof.



232

233 **Figure 14.** Structural plan of the proposed model house (Note: All dimensions are in mm)

234 Individual mould method (BIS, 2016) is opted for the casting process of elements. Wooden moulds
 235 are prepared as per the requirement such that each mould can be re-used multiple times for casting,
 236 intending to make the casting process time and resource saving. These moulds are shown in the
 237 Figures 15 and 16. They are oiled before casting and are repaired and cleaned after demoulding
 238 for casting the next set of panels.



Figure 15. Wooden moulds



Figure 16. Oiling of moulds

239

240 ***4.2 Casting, handling, curing and stacking***

241 Eight batches of concrete and 30 batches of LW mix are prepared in their respective mixers and
242 by placing them in the wooden moulds with required reinforcements (Fig. 17 and 18). Workability
243 was inspected during the castings and the concrete and LW mixes have resulted in a medium and
244 low degree of workability through the slump cone test. Each casting from the mixer was placed
245 into the moulds within 30 minutes from addition of water into the mix.

246 As per the structural calculations, a minimum reinforcement criterion was satisfied by placing one
247 reinforcement bar of 8mm diameter in the centre of concrete columns and beams, whereas a layer
248 of steel grid mesh was inserted in between LW prefab panels.

249 The door, window, and ventilator openings are provided while casting as per the drawings
250 mentioned in Figure 19. Sample pipe fittings for electrical and plumbing requirements are also
251 incorporated as shown in Figure 20.



Figure 17. Casting of structural elements



Figure 18. Casting of prefab panels

252



Figure 19. Provision for window opening



Figure 20. Provision of pipe fitting

253



Figure 21. Curing of concrete elements



Figure 22. Curing and stacking of prefab panels

254

255 Concrete beams and columns are placed into the water bath for curing (Fig. 21). Whereas, prefab
256 panels are stacked one against each other vertically and are cured with the help of soaked gunny
257 bags (Fig. 22). Age of curing for all the elements is 28 days after which elements are ready for
258 application on site.

259 ***4.3 Transport, plotting, erection and jointing***

260 The concrete elements and prefab panels are loaded into the trucks for their transport to the site.
261 The area is plotted as per the plan and the ground is cleared and levelled. As the model is a framed
262 structure, columns and beams are first erected followed by wall panels (Fig. 23). For placing
263 columns, small grooves are made on the surface such that columns are fit into them. Beams have
264 slots at the ends. The adjacent beams are placed into them and grouted. Jointing of both the
265 concrete and prefab elements is done through application of polymer-based epoxy grout (Fig. 24).
266 Small finishing works such as filling up of gaps between the elements are done by application of
267 cement mortar.



Figure 23. Erection of structural elements and wall panels



Figure 24. Application of Epoxy grout



Figure 25. Erection of roof supporting elements

268



Figure 26. Erection of slab panels



Figure 27. PV panel embedded into roof

269

270 Roofing members are erected after a day of erection of roof supporting elements (TRP 1-6) such
 271 that the grout is properly set and hardened (Fig. 25 and 26). As this model is small-scale, the
 272 elements and panels were handled and erected manually. By scaling up the model to real-scale,
 273 handling can be mechanized in view of its increased size and weight for which handling stress can
 274 be evaluated further.

275 Roofing members of south elevation have the provision for the PV panel to be integrated into the
276 roof. A day after the roofing members are erected, the proposed PV panel is fixed into the groove
277 provided with the help of polyurethane foam (Fig. 27). The electrical cables are arranged such that
278 they are inserted through the roof into the model house without getting effected by any kind of
279 climatic and environmental conditions. The openings are furnished with wooden doors, and
280 wooden framed glass windows. Figures 28 and 29 indicate the constructed prefabricated housing
281 model.

282



Figure 28. Front (North) elevation of model house



Figure 29. Backside (South) of model house

283

284 A time-duration study is conducted through analytical tools by considering activities starting from
285 material acquisition to the erection of the model house. Labour output was included in this study
286 based on an Indian standard code (IS:7272-1(1974), 1974). Results depict that erection of the
287 designed prefabricated model house is 20% faster than the conventional construction that involves
288 cast in-situ concreting and brickwork.

289 **5. Conclusion and recommendations**

290 This study proposes a novel, sustainable, and lightweight product to be used as a walling member.
291 An agro-industrial by-product namely CFA was used as a sustainable alternative to the naturally
292 available resource. This alternate material has potential application to be mixed in design of both
293 concrete and lightweight prefab elements. This study mainly focusses on development of
294 lightweight prefabricated walling elements and analysing its suitability over the commercially
295 available products. Accordingly, tests related to physico-mechanical properties (density, water
296 absorption, compressive strength, split tensile strength, and flexural strength), durability (chloride
297 permeability), thermal conductivity, and workability were performed as per the standards. Based
298 on compliance criteria, it is concluded that the proposed end-products are sustainable alternatives
299 to commercially available construction products, and suitable for real-time construction. The
300 comparative study resulted the proposed end-product as 18% and 27% lighter than burnt clay and
301 fly ash bricks respectively. The lightweight prefab panel resulted in 0.7% and 8.5% higher
302 compressive strength over burnt clay brick and fly ash brick respectively. Similarly, the
303 comparison of thermal property for lightweight prefab panel resulted in 68% and 62% less
304 conductivity than burnt clay and fly ash bricks respectively. However, the connections during the
305 model house erection were made with epoxy-based grout that can be replaced with mechanical
306 connections for the scaled-up model houses. Furthermore, an energy calculation regarding solar
307 PV panel embedded into the roof indicates that a ceiling fan and a tube-light can be accommodated
308 by considering 71% of its energy generation under provided assumptions. Prefab construction is
309 found effective in reducing the total duration of the project by around 20% in comparison to the
310 conventional construction. Overall, the lightweight end-product proposed as a prefab walling
311 member was successfully cast and erected as a small-scale experimental model house.

312 **Funding:** This research was supported by funding under the grant LJMU GCRF fund—271002/
313 S0001/954FET/GCRFFET04.

314 **Acknowledgments:** This research is supported by funding under the grant LJMU Global
315 Challenge Research Fund 2018–2020. The experimentation and castings were conducted with the
316 support of M/s. Apple Chemie India Pvt Ltd.

317 **Conflicts of Interest:** The authors declare no conflict of interest.

318 **References**

319 Amran, Y. H. M. *et al.* (2016) ‘Response of precast foamed concrete sandwich panels to flexural
320 loading’, *Journal of Building Engineering*, 7, pp. 143–158. doi: 10.1016/j.jobbe.2016.06.006.

321 BIS (2016) ‘National Building Code of India, 2016 Volume 1’, *National Building Code of India*,
322 80, p. 1 v. (various pagings).

323 Bras, A. *et al.* (2020) ‘Sustainable and affordable prefab housing systems with minimal whole life
324 energy use’, *Energy and Buildings*, 220, p. 110030. doi: 10.1016/J.ENBUILD.2020.110030.

325 Chippagiri, R. *et al.* (2021) ‘Application of Sustainable Prefabricated Wall Technology for Energy
326 Efficient Social Housing’, *Sustainability*, 13(1195). doi: <https://doi.org/10.3390/su13031195>.

327 Correia, J. R., Ferreira, J. and Branco, F. A. (2006) ‘A rehabilitation study of sandwich GRC facade
328 panels’, *Construction and Building Materials*, 20(8), pp. 554–561. doi:
329 10.1016/j.conbuildmat.2005.01.066.

330 Dakwale, V. A. and Ralegaonkar, R. V. (2014) ‘Development of sustainable construction material
331 using construction and demolition waste’, *Indian Journal of Engineering and Materials Sciences*,

332 21(4), pp. 451–457.

333 Daniel Ronald Joseph, J., Prabakar, J. and Alagusundaramoorthy, P. (2018) ‘Flexural behavior of
334 precast concrete sandwich panels under different loading conditions such as punching and
335 bending’, *Alexandria Engineering Journal*, 57(1), pp. 309–320. doi: 10.1016/j.aej.2016.11.016.

336 Dave, M., Watson, B. and Prasad, D. (2017) ‘Performance and perception in prefab housing: An
337 exploratory industry survey on sustainability and affordability’, *Procedia Engineering*, 180, pp.
338 676–686. doi: 10.1016/j.proeng.2017.04.227.

339 Department of Economic and Social Affairs, U. N. (no date) *India Population (2020) [Internet]*.
340 Available at: <https://www.worldometers.info/world-population/india-population/> (Accessed: 12
341 March 2020).

342 ECBC (2017) ‘Energy Conservation Building Code’, *Bureau of Energy Efficiency*.

343 Einea, A. *et al.* (1991) ‘State-of-the-art of Precast Concrete Sandwich Panels’, *PCI Journal*, 36(6),
344 pp. 78–92. doi: 10.15554/pcij.11011991.78.98.

345 Ferdous, W. *et al.* (2019a) ‘New advancements, challenges and opportunities of multi-storey
346 modular buildings – A state-of-the-art review’, *Engineering Structures*, 183, pp. 883–893. doi:
347 10.1016/J.ENGSTRUCT.2019.01.061.

348 Ferdous, W. *et al.* (2019b) ‘New advancements, challenges and opportunities of multi-storey
349 modular buildings – A state-of-the-art review’, *Engineering Structures*, 183(October 2018), pp.
350 883–893. doi: 10.1016/j.engstruct.2019.01.061.

351 Flansbjerg, M. *et al.* (2018) ‘Composite Behaviour of Textile Reinforced Reactive Powder Concrete

352 Sandwich Façade Elements’, *International Journal of Concrete Structures and Materials*, 12(1).
353 doi: 10.1186/s40069-018-0301-4.

354 Gavali, H. R. *et al.* (2019) ‘Development of sustainable alkali-activated bricks using industrial
355 wastes’, *Construction and Building Materials*, 215, pp. 180–191. doi:
356 10.1016/j.conbuildmat.2019.04.152.

357 Gavali, H. R. and Ralegaonkar, R. V. (2020) ‘Design of eco-efficient housing with sustainable
358 alkali-activated bricks’, *Journal of Cleaner Production*, 254, p. 120061. doi:
359 10.1016/j.jclepro.2020.120061.

360 Grandoliniede, G. M. and Ijjasz-Vasquez, E. (2016) *3 reasons why ‘Housing for All’ can happen*
361 *by 2030*. Available at: [https://blogs.worldbank.org/voices/3-reasons-why-housing-all-can-happen-](https://blogs.worldbank.org/voices/3-reasons-why-housing-all-can-happen-2030)
362 [2030](https://blogs.worldbank.org/voices/3-reasons-why-housing-all-can-happen-2030) (Accessed: 5 August 2021).

363 I. Goh, W. *et al.* (2016) ‘Finite Element Analysis of Precast Lightweight Foamed Concrete
364 Sandwich Panel Subjected to Axial Compression’, *Journal of Computer Science & Computational*
365 *Mathematics*, (February), pp. 1–9. doi: 10.20967/jcscm.2016.01.001.

366 IS:2185 (2005) ‘Concrete masonry units, Part 1: Hollow and solid concrete blocks’, *Bureau of*
367 *Indian Standards, New Delhi*, p. 17.

368 IS:7272-1(1974) (1974) ‘Recommendation for Labour Output Constants for Building Work, Part
369 I: North Zone’, *Bureau of Indian Standards, New Delhi*.

370 IS 456: 2000 (no date) ‘Plain and Reinforced Concrete - Code of Practice’, *Bureau of Indian*
371 *Standards, New Delhi*, pp. 1–114.

372 Krishnanunny, M. and K, A. K. (2018) ‘Prefab technology a solution to existing challenges in
373 construction sector of India - A Kerala perspective’, *International Journal of Pure and Applied*
374 *Mathematics*, 119(15), pp. 1339–1347. Available at: <http://www.acadpubl.eu/hub/>.

375 Kulshreshtha, Y. *et al.* (2020) ‘The potential and current status of earthen material for low-cost
376 housing in rural India’, *Construction and Building Materials*, 247, p. 118615. doi:
377 10.1016/j.conbuildmat.2020.118615.

378 Kumar Gangaram Singh, M. and Kizhakkumodom Venkatanarayanan, H. (2020) ‘Performance of
379 Self-Consolidating High-Strength Mortars Developed from Portland Pozzolana Cement for
380 Precast Applications’, *Journal of Materials in Civil Engineering*, 32(3), p. 04019375. doi:
381 10.1061/(asce)mt.1943-5533.0003041.

382 Kumar, K. R. *et al.* (2021) ‘Cleaner production of self-compacting concrete with selected industrial
383 rejects-an overview’, *Silicon*, 13(8), pp. 2809–2820. doi: 10.1007/s12633-020-00636-6.

384 Li, Z., Shen, G. Q. and Xue, X. (2014) ‘Critical review of the research on the management of
385 prefabricated construction’, *Habitat International*, 43, pp. 240–249. doi:
386 10.1016/j.habitatint.2014.04.001.

387 Liu, M., Jia, S. and Liu, X. (2019) ‘Evaluation of mitigation potential of GHG emissions from the
388 construction of prefabricated subway station’, *Journal of Cleaner Production*, 236, p. 117700. doi:
389 10.1016/j.jclepro.2019.117700.

390 Lopez, D. and Froese, T. M. (2016) ‘Analysis of costs and benefits of panelized and modular
391 prefabricated homes’, *Procedia Engineering*, 145, pp. 1291–1297. doi:
392 10.1016/j.proeng.2016.04.166.

393 Madurwar, M. V., Mandavgane, S. A. and Ralegaonkar, R. V. (2015) ‘Development and feasibility
394 analysis of bagasse ash bricks’, *Journal of Energy Engineering*, 141(3), pp. 1–9. doi:
395 10.1061/(ASCE)EY.1943-7897.0000200.

396 Ministry of Housing & Urban Poverty Alleviation Government of India (2017) ‘Pradhan Mantri
397 Awas Yojana - Housing for All (Urban) - Credit Linked Subsidy Scheme’, 2017, pp. 1–62.
398 Available at: http://mhupa.gov.in/pmay/repository/01_PMAY_Guidelines_English.pdf.

399 Naito, C. *et al.* (2012) ‘Performance and characterization of shear ties for use in insulated precast
400 concrete sandwich wall panels’, *Journal of Structural Engineering (United States)*, 138(1), pp. 52–
401 61. doi: 10.1061/(ASCE)ST.1943-541X.0000430.

402 Nath, A. J., Lal, R. and Das, A. K. (2018) ‘Fired Bricks: CO₂ Emission and Food Insecurity’,
403 *Global Challenges*, 2(4), p. 1700115. doi: 10.1002/gch2.201700115.

404 Ram, S., Ralegaonkar, R. V. and Pradhan, K. (2017) ‘Use of co-fired blended ash in the
405 development of sustainable construction materials’, *Proceedings of the Institution of Civil
406 Engineers: Engineering Sustainability*, 171(8), pp. 425–432. doi: 10.1680/jensu.17.00008.

407 Rathod, N. *et al.* (2020) ‘Development of Sustainable Masonry Blocks Using Industrial Rejects
408 and Alkali Activation’, in *International Conference on Innovative Technologies for Clean and
409 Sustainable Development*. Chandigarh, India: Springer, pp. 357–368. doi:
410 https://doi.org/10.1007/978-3-030-51485-3_24.

411 Raut, S. P. *et al.* (2012) ‘Reuse of recycle paper mill waste in energy absorbing light weight bricks’,
412 *Construction and Building Materials*, 27(1), pp. 247–251. doi:
413 10.1016/j.conbuildmat.2011.07.053.

414 Van Ruijven, B. J. *et al.* (2016) ‘Long-term model-based projections of energy use and CO₂
415 emissions from the global steel and cement industries’, *Resources, Conservation and Recycling*,
416 112, pp. 15–36. doi: 10.1016/j.resconrec.2016.04.016.

417 Sakhare, V. V. and Ralegaonkar, R. V. (2016a) ‘Use of bio-briquette ash for the development of
418 bricks’, *Journal of Cleaner Production*, 112, pp. 684–689. doi: 10.1016/J.JCLEPRO.2015.07.088.

419 Sakhare, V. V. and Ralegaonkar, R. V. (2016b) ‘Use of bio-briquette ash for the development of
420 bricks’, *Journal of Cleaner Production*, 112, pp. 684–689. doi: 10.1016/j.jclepro.2015.07.088.

421 Sakhare, V. V. and Ralegaonkar, R. V. (2018) ‘Strategy to control indoor temperature for
422 redevelopment of slum dwellings’, *Indoor and Built Environment*, 27(9), pp. 1203–1215. doi:
423 10.1177/1420326X17712107.

424 Shams, A. *et al.* (2015) ‘Innovative sandwich structures made of high performance concrete and
425 foamed polyurethane’, *Composite Structures*, 121, pp. 271–279. doi:
426 10.1016/j.compstruct.2014.11.026.

427 Shelote, K. M. *et al.* (2021) ‘Utilization of co-fired blended ash and chopped basalt fiber in the
428 development of sustainable mortar’, *Sustainability (Switzerland)*, 13(3), pp. 1–19. doi:
429 10.3390/su13031247.

430 Singla, R., Kumar, S. and Alex, T. C. (2020) ‘Reactivity Alteration of Granulated Blast Furnace
431 Slag by Mechanical Activation for High Volume Usage in Portland Slag Cement’, *Waste and
432 Biomass Valorization*, 11(6), pp. 2983–2993. doi: 10.1007/s12649-019-00580-6.

433 Steinhardt, D. A. and Manley, K. (2016) ‘Adoption of prefabricated housing—the role of country

434 context', *Sustainable Cities and Society*, 22, pp. 126–135. doi: 10.1016/J.SCS.2016.02.008.

435 United Nations (2019) *UN Climate Action Summit 2019 [Internet]*, *un.org*. Available at:

436 <https://www.un.org/en/climatechange/un-climate-summit-2019.shtml>.

437